Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of Work: Restoration and Improvements of Mahalakshmi layout, Balaji layout, Best ounty, Bhaskar Reddy, Andhra layout, Thirumala nagara and surrounding areas in ward no - 03 of Yelahanka New town Sub division PACKAGE NO-10

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Civil Work								
KSRRB300-1. **Earthwork excavation** by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.(I.NO 19.1,Page no 143 SR 2018-19)								
Basic rate	130.00							
Area Weightage 6%	7.80							
Loading and Unloading & Lead,8KM, (57+ 2*1.28*8)	77.48							
Total	**215.28**							
	Cum							
For RCC DRAIN								
Ananthapura								
1st Cross Road		1	44.50	1.00	1.00	44.50		
2nd Cross Road		1	57.50	1.00	1.00	57.50		
Mahalakshmi Layout								
Manjushree Darshini Hotel Rd (W0095)		2	40.00	1.10	1.00	88.00		
Vinayaka Medicals Rd (W0111)		2	109.00	1.10	1.00	239.80		
Centurey Appartment Connecting Rd		2	125.00	1.10	1.00	275.00		
Cross Rd		2	63.00	1.10	1.00	138.60		
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00	1.90	2.10	2034.90		
Ananthapura								
11th Main Road (W0041)		1	102.00	1.10	1.00	112.20		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		2	71.00	1.10	1.00	156.20		
2nd A Main Rd, 4th Cross Rd		2	140.00	1.10	1.00	308.00		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	1.10	1.00	200.20		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	1.10	1.10	220.22		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	1.10	1.00	222.20		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	1.10	1.00	200.20		
1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	1.10	1.10	174.24		
Cross Rd		2	170.00	1.10	1.00	374.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00	1.00	1.00	240.00		
Best County II								
2nd Cross Road (W0434)		2	91.00	1.10	1.00	200.20		
Best County III								
2nd Main Road(W0781)		1	187.00	1.10	1.00	205.70		
Cross Rd		2	147.00	1.10	1.00	323.40		
Deo Marvel Layout								
3rd Main Rd								
3rd Cross Rd (WO167)		2	37.00	1.00	1.00	74.00		
4th Cross Rd (W0169)		2	35.00	1.00	1.00	70.00		
Ananthapura								
Manito Northlite Rd		2	65.00	1.00	1.00	130.00		
Krishna Enclave Rd (W0163)		1	75.00	1.00	1.00	75.00		
Deo Marvel Layout								
3rd Main Rd								
2nd Cross Rd (W0161)		2	37.00	1.00	1.00	74.00		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00	1.10	1.00	242.00		
Cross Rd-1		2	27.00	1.10	1.00	59.40		
2nd Cross Rd		2	108.00	1.10	1.00	237.60		
Cross Rd		2	100.00	1.10	1.00	220.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00	1.10	1.00	697.40		
Burial Ground UptoVillage Road (W0296)		2	293.00	1.10	1.00	644.60		
For KERB stone								
Ananthapura								
11th Main Road (W0041)		2	380.00	0.20	0.30	45.60		
Peeple Tree Rd (W0079)		1	400.00	0.20	0.30	24.00		
Bhaskar Reddy Layout								
2nd Main Road		2	162.00	0.20	0.30	19.44		
4th Cross Rd		2	68.00	0.20	0.30	8.16		
3rd A Cross Rd (W0028)		2	63.00	0.20	0.30	7.56		
2nd Cross Road (W0030)		2	208.00	0.20	0.30	24.96		
2nd A Cross Road (W0032)		2	59.00	0.20	0.30	7.08		
3rd Cross Road (W0026)		2	73.00	0.20	0.30	8.76		
For RCC CULVERT								
		3	6.10	1.50	1.00	27.45		
Attur lake Rd		3	6.50	2.10	1.30	53.24		
		11	7.20	1.80	1.30	185.33		
Bhaskar Reddy Layout		5	6.70	1.50	1.00	50.25		
Best County III		3	6.50	1.50	1.00	29.25		
Balaji Layout		6	7.10	1.50	0.90	57.51		
						8887.64		
Deduct 15% Existing Drain Earthwork						1333.15		
						7554.50		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Veerasagar Hesargatta Road								
LHS		1	786.00	1.10	1.00	864.60		
RHS		1	705.00	1.10	1.00	775.50		
Road 4		2	48.00	1.10	1.00	105.60		
2nd Cross		2	353.00	1.10	1.00	776.60		
For RCC CULVERT								
		12	6.25	1.80	1.00	135.00		
Box Culvert for Lake		1	8.00	3.30	2.50	66.00		
Retaining wall for Box Culvert		2	5.00	2.70	2.50	67.50		
						2790.80		
Deduct 10% Existing Drain Earthwork						279.08		
						2511.72		
						10066.22	**215.28**	**2167055.10**
KSRB 2.8 : Providing and Filling in **foundation with granite / trap broken metal 100mm.** and down size & with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. specification.(P.No-7,I No-2.15 of PWD BCSR 2018-19)								
Basic Rate	2429.00							
6% Area weightage	145.74							
Total	**2574.74**							
	Cum							
Ananthapura								
From Attur lake Rd Upto SWD		1	510.00	1.90	0.25	242.25		
						242.25	**2574.74**	**623730.77**
KSRB 4-1.3 : Providing and laying in position **plain cement concrete of Mix 1:4:8** with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.No-13,I No-4.3 of PWD BCSR 2018-19)								
Basic Rate	5102.00							
3.6*55.47	199.69							
Sub total	5301.69							
6% Area weightage	318.10							
Total	**5619.79**							
	Cum							
For RCC DRAIN								
Ananthapura								
1st Cross Road		1	44.50	1.00	0.15	6.68		
2nd Cross Road		1	57.50	1.00	0.15	8.63		
Mahalakshmi Layout								
Manjushree Darshini Hotel Rd (W0095)		2	40.00	1.10	0.15	13.20		
Vinayaka Medicals Rd (W0111)		2	109.00	1.10	0.15	35.97		
Centurey Appartment Connecting Rd		2	125.00	1.10	0.15	41.25		
Cross Rd		2	63.00	1.10	0.15	20.79		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00	1.90	0.15	145.35		
Ananthapura								
11th Main Road (W0041)		1	102.00	1.10	0.15	16.83		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		2	71.00	1.10	0.15	23.43		
2nd A Main Rd, 4th Cross Rd		2	140.00	1.10	0.15	46.20		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	1.10	0.15	30.03		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	1.10	0.15	30.03		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	1.10	0.15	33.33		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	1.10	0.15	30.03		
1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	1.10	0.15	23.76		
Cross Rd		2	170.00	1.10	0.15	56.10		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00	1.00	0.15	36.00		
Best County II								
2nd Cross Road (W0434)		2	91.00	1.10	0.15	30.03		
Best County III								
2nd Main Road(W0781)		1	187.00	1.10	0.15	30.86		
Cross Rd		2	147.00	1.10	0.15	48.51		
Deo Marvel Layout								
3rd Main Rd								
3rd Cross Rd (WO167)		2	37.00	1.00	0.15	11.10		
4th Cross Rd (W0169)		2	35.00	1.00	0.15	10.50		
Ananthapura								
Manito Northlite Rd		2	65.00	1.00	0.15	19.50		
Krishna Enclave Rd (W0163)		1	75.00	1.00	0.15	11.25		
Deo Marvel Layout								
3rd Main Rd								
2nd Cross Rd (W0161)		2	37.00	1.00	0.15	11.10		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00	1.10	0.15	36.30		
Cross Rd-1		2	27.00	1.10	0.15	8.91		
2nd Cross Rd		2	108.00	1.10	0.15	35.64		
Cross Rd		2	100.00	1.10	0.15	33.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00	1.10	0.15	104.61		
Burial Ground UptoVillage Road (W0296)		2	293.00	1.10	0.15	96.69		
Veerasagar Hesargatta Road								
LHS		1	786.00	1.10	0.15	129.69		
RHS		1	705.00	1.10	0.15	116.33		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Road 4		2	48.00	1.10	0.15	15.84		
2nd Cross		2	353.00	1.10	0.15	116.49		
For RCC CULVERT								
		3	6.10	1.50	0.15	4.12		
Attur lake Rd		3	6.50	2.10	0.15	6.14		
		11	7.20	1.80	0.15	21.38		
Bhaskar Reddy Layout		5	6.70	1.50	0.15	7.54		
Best County III		3	6.50	1.50	0.15	4.39		
Balaji Layout		6	7.10	1.50	0.15	9.59		
		12	6.25	1.80	0.15	20.25		
Box Culvert for Lake		1	8.00	3.30	0.20	5.28		
Retaining wall for Box Culvert		2	5.00	2.70	0.20	5.40		
For Footpath								
Veerasagar Hesargatta Road		2	993.00	0.65	0.15	193.64		
2nd Cross		2	353.00	0.30	0.15	31.77		
						1773.43	**5619.79**	**9966304.80**
KSRRB M2200-6. Providing **TMT Bars Fe 500 steel reinforcement for R.C.C.** work including straightening, cutting, bending, hooking, placing in postion, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification.(I.NO 28.8.2 Page no 229, SR 2018-19)								
Basic Rate	75610.00							
Area Weightage 6%	4536.60							
	80146.60							
	Tn							
Consider 60kg/cum for drain		1	2578.23		0.06	154.69		
Consider 80kg/cum for culvert		1	189.28		0.08	15.14		
Consider 90kg/cum for Attur Lake Rd		1	420.75		0.09	37.87		
Consider 90kg/cum for Box culvert slab		1	8.42		0.09	0.76		
						208.46	**80146.60**	**16707473.24**
Providing and laying **plain/reinforced cement concrete for side drains using M20** nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19)								
Basic rate	6670.00							
6*55.47	332.82							
Sub total	7002.82							
6% Area weightage	420.17							
Total	**7422.99**							
	Cum							
For RCC DRAIN RAFT								
Ananthapura								
1st Cross Road		1	44.50	0.80	0.15	5.34		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd Cross Road		1	57.50	0.80	0.15	6.90		
Mahalakshmi Layout								
Manjushree Darshini Hotel Rd (W0095)		2	40.00	0.90	0.15	10.80		
Vinayaka Medicals Rd (W0111)		2	109.00	0.90	0.15	29.43		
Centurey Appartment Connecting Rd		2	125.00	0.90	0.15	33.75		
Cross Rd		2	63.00	0.90	0.15	17.01		
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00	1.50	0.15	114.75		
Ananthapura								
11th Main Road (W0041)		1	102.00	0.90	0.15	13.77		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		2	71.00	0.90	0.15	19.17		
2nd A Main Rd, 4th Cross Rd		2	140.00	0.90	0.15	37.80		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	0.90	0.15	24.57		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	0.90	0.15	24.57		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	0.90	0.15	27.27		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	0.90	0.15	24.57		
1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	0.90	0.15	19.44		
Cross Rd		2	170.00	0.90	0.15	45.90		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00	0.80	0.15	28.80		
Best County II								
2nd Cross Road (W0434)		2	91.00	0.90	0.15	24.57		
Best County III								
2nd Main Road(W0781)		1	187.00	0.90	0.15	25.25		
Cross Rd		2	147.00	0.90	0.15	39.69		
Deo Marvel Layout								
3rd Main Rd								
3rd Cross Rd (WO167)		2	37.00	0.80	0.15	8.88		
4th Cross Rd (W0169)		2	35.00	0.80	0.15	8.40		
Ananthapura								
Manito Northlite Rd		2	65.00	0.80	0.15	15.60		
Krishna Enclave Rd (W0163)		1	75.00	0.80	0.15	9.00		
Deo Marvel Layout								
3rd Main Rd								
2nd Cross Rd (W0161)		2	37.00	0.80	0.15	8.88		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00	0.90	0.15	29.70		
Cross Rd-1		2	27.00	0.90	0.15	7.29		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd Cross Rd		2	108.00	0.90	0.15	29.16		
Cross Rd		2	100.00	0.90	0.15	27.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00	0.90	0.15	85.59		
Burial Ground UptoVillage Road (W0296)		2	293.00	0.90	0.15	79.11		
Veerasagar Hesargatta Road								
LHS		1	786.00	0.90	0.15	106.11		
RHS		1	705.00	0.90	0.15	95.18		
Road 4		2	48.00	0.90	0.15	12.96		
2nd Cross		2	353.00	0.90	0.15	95.31		
For RCC DRAIN WALL								
Ananthapura								
1st Cross Road		2	44.50	0.15	0.60	8.01		
2nd Cross Road		2	57.50	0.15	0.60	10.35		
Mahalakshmi Layout								
Manjushree Darshini Hotel Rd (W0095)		4	40.00	0.15	0.60	14.40		
Vinayaka Medicals Rd (W0111)		4	109.00	0.15	0.70	45.78		
Centurey Appartment Connecting Rd		4	125.00	0.15	0.65	48.75		
Cross Rd		4	63.00	0.15	0.60	22.68		
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		2	510.00	0.20	1.50	306.00		
Ananthapura								
11th Main Road (W0041)		2	102.00	0.15	0.60	18.36		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		4	71.00	0.15	0.60	25.56		
2nd A Main Rd, 4th Cross Rd		4	140.00	0.15	0.60	50.40		
2nd A Main Rd, 2nd Cross Rd (W0045)		4	91.00	0.15	0.60	32.76		
2nd A Main Rd, 5th Cross Rd (W0063)		4	91.00	0.15	0.60	32.76		
2nd A Main Rd, 5th A Cross Rd (W0067)		4	101.00	0.15	0.60	36.36		
2nd A Main Rd, 3rd Cross Rd (W0055)		4	91.00	0.15	0.60	32.76		
1st Main Rd, 4th A Cross Rd (W0024)		4	72.00	0.15	0.60	25.92		
Cross Rd		4	170.00	0.15	0.60	61.20		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		4	120.00	0.15	0.60	43.20		
Best County II								
2nd Cross Road (W0434)		4	91.00	0.15	0.60	32.76		
Best County III								
2nd Main Road(W0781)		2	187.00	0.15	0.60	33.66		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Cross Rd		4	147.00	0.15	0.60	52.92		
Deo Marvel Layout								
3rd Main Rd								
3rd Cross Rd (WO167)		4	37.00	0.15	0.60	13.32		
4th Cross Rd (W0169)		4	35.00	0.15	0.60	12.60		
Ananthapura								
Manito Northlite Rd		4	65.00	0.15	0.60	23.40		
Krishna Enclave Rd (W0163)		2	75.00	0.15	0.60	13.50		
Deo Marvel Layout								
3rd Main Rd								
2nd Cross Rd (W0161)		4	37.00	0.15	0.60	13.32		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		4	110.00	0.15	0.60	39.60		
Cross Rd-1		4	27.00	0.15	0.60	9.72		
2nd Cross Rd		4	108.00	0.15	0.60	38.88		
Cross Rd		4	110.00	0.15	0.60	39.60		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		4	317.00	0.15	0.70	133.14		
Burial Ground UptoVillage Road (W0296)		4	293.00	0.15	0.70	123.06		
Veerasagar Hesargatta Road								
LHS		2	786.00	0.15	0.60	141.48		
RHS		2	705.00	0.15	0.60	126.90		
Road 4		4	48.00	0.15	0.60	17.28		
2nd Cross		4	353.00	0.15	0.60	127.08		
						2998.98		
For RCC CULVERT RAFT								
		3	6.10	1.20	0.20	4.39		
Attur lake Rd		3	6.50	1.80	0.20	7.02		
		11	7.20	1.50	0.20	23.76		
Bhaskar Reddy Layout		5	6.70	1.20	0.20	8.04		
Best County III		3	6.50	1.20	0.20	4.68		
Balaji Layout		6	7.10	1.20	0.20	10.22		
		12	6.25	1.80	0.20	27.00		
Box Culvert for Lake		1	8.00	3.00	0.25	6.00		
Retaining wall for Box Culvert		2	5.00	2.40	0.30	7.20		
For RCC CULVERT WALL								
		6	6.10	0.23	0.50	4.21		
Attur lake Rd		6	6.50	0.23	0.75	6.73		
		22	7.20	0.23	0.75	27.32		
Bhaskar Reddy Layout		10	6.70	0.23	0.50	7.71		
Best County III		6	6.50	0.23	0.50	4.49		
Balaji Layout		12	7.10	0.23	0.50	9.80		
		24	6.25	0.23	0.60	20.70		
Box Culvert for Lake		2	8.00	0.30	1.80	8.64		
Retaining wall for Box Culvert		2	5.00	0.23	0.60	1.38		
						189.28		
						3188.26	7422.99	23666452.95

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Providing and Placing Reinforced / Prestressed cement concrete in super-structure as per drawing and Technical Specification complete as per specifications. B. **RCC with OPC cement design mix M25 @ 340kgs**, with 20mm and down size graded granite metal coarse aggregates @0.7cum and fine aggregates @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed- 2008, including cost of materials, labour, HOM, Curing, form works, scaffolding and centering complete as per specification Height upto 5 m. (Pg No 233 It No 29.5.1 of PWD SR 2018-19)								
Basic rate	6418.00							
6.8*55.47	377.20							
Sub total	6795.20							
6% Area weightage	407.71							
Total	**7202.91**							
	Cum							
Box Culvert for Lake		1	8.00	3.00	0.30	7.20		
Crash Barrier		2	3.00	0.23	0.90	1.22		
						8.42	**7202.91**	**60,612.47**
Providing and Fixing **Pre cast covering Slab 100mm thick** made out of CC, jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)								
Data rate	**1922.00**							
	Sqm							
For RCC DRAIN COVERING SLAB								
Mahalakshmi Layout								
Centurey Appartment Connecting Rd		2	125.00	0.90		225.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00	0.90		570.60		
Burial Ground UptoVillage Road (W0296)		2	293.00	0.90		527.40		
						1323.00		
Ananthapura								
1st Cross Road		1	44.50	0.75		33.38		
2nd Cross Road		1	57.50	0.75		43.13		
Manjushree Darshini Hotel Rd (W0095)		2	40.00	0.90		72.00		
Vinayaka Medicals Rd (W0111)		2	109.00	0.90		196.20		
Cross Rd		2	63.00	0.90		113.40		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		2	71.00	0.90		127.80		
2nd A Main Rd, 4th Cross Rd		2	140.00	0.90		252.00		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	0.90		163.80		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	0.90		163.80		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	0.90		181.80		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	0.90		163.80		
1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	0.90		129.60		
Cross Rd		2	170.00	0.90		306.00		
Ananthapura								
11th Main Road (W0041)								
Peeple Tree Rd (W0079)		1	102.00	0.90		91.80		
Deo Marvel Layout		1	400.00	0.90		360.00		
3rd Main Rd								
1st Cross rd								
Best County II		2	120.00	0.75		180.00		
2nd Cross Road (W0434)								
Best County III		2	91.00	0.90		163.80		
2nd Main Road(W0781)								
Cross Rd		1	187.00	0.90		168.30		
Deo Marvel Layout		2	147.00	0.90		264.60		
3rd Main Rd								
3rd Cross Rd (WO167)								
4th Cross Rd (W0169)		2	37.00	0.75		55.50		
Ananthapura		2	35.00	0.75		52.50		
Manito Northlite Rd								
Krishna Enclave Rd (W0163)		2	65.00	0.75		97.50		
Deo Marvel Layout		1	75.00	0.75		56.25		
3rd Main Rd								
2nd Cross Rd (W0161)								
Muneshwara Layout		2	37.00	0.75		55.50		
11th Main Road								
1st Cross Rd								
Cross Rd-1		2	110.00	0.90		198.00		
2nd Cross Rd		2	27.00	0.90		48.60		
Cross Rd		2	108.00	0.90		194.40		
		2	100.00	0.90		180.00		
						4113.45		
			Consider 80%			**3290.76**		
Veerasagar Hesargatta Road								
LHS		1	786.00	0.90		707.40		
RHS		1	705.00	0.90		634.50		
Road 4		2	48.00	0.90		86.40		
2nd Cross		2	353.00	0.90		635.40		
						2063.70		
			Consider 90%			**1857.33**		
						6471.09	1922.00	12437434.98
Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)								
Basic rate	105.00							
Area Weightage 6%	6.30							
Total	**111.30**							
	Sqm							
Ananthapura								
1st Cross Road		1	44.50	0.75		33.38		
2nd Cross Road		1	57.50	0.75		43.13		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Manjushree Darshini Hotel Rd (W0095)								
Vinayaka Medicals Rd (W0111)		2	40.00	0.90		72.00		
Vinayaka Medicals Rd		2	109.00	0.90		196.20		
Cross Rd		2	63.00	0.90		113.40		
Bhaskar Reddy Layout								
2nd A Main Rd (W0022)		2	71.00	0.90		127.80		
2nd A Main Rd, 4th Cross Rd		2	140.00	0.90		252.00		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	0.90		163.80		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	0.90		163.80		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	0.90		181.80		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	0.90		163.80		
1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	0.90		129.60		
Cross Rd		2	170.00	0.90		306.00		
Ananthapura								
11th Main Road (W0041)		1	102.00	0.90		91.80		
Peeple Tree Rd (W0079)		1	400.00	0.90		360.00		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00	0.75		180.00		
Best County II								
2nd Cross Road (W0434)		2	91.00	0.90		163.80		
Best County III								
2nd Main Road(W0781)		1	187.00	0.90		168.30		
Cross Rd		2	147.00	0.90		264.60		
Deo Marvel Layout								
3rd Main Rd								
3rd Cross Rd (WO167)		2	37.00	0.75		55.50		
4th Cross Rd (W0169)		2	35.00	0.75		52.50		
Ananthapura								
Manito Northlite Rd		2	65.00	0.75		97.50		
Krishna Enclave Rd (W0163)		1	75.00	0.75		56.25		
Deo Marvel Layout								
3rd Main Rd								
2nd Cross Rd (W0161)		2	37.00	0.75		55.50		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00	0.90		198.00		
Cross Rd-1		2	27.00	0.90		48.60		
2nd Cross Rd		2	108.00	0.90		194.40		
Cross Rd		2	100.00	0.90		180.00		
						4113.45		
Deduct 80% New Slabs						3290.76		
						822.69		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Veerasagar Hesargatta Road								
LHS		1	786.00	0.90		707.40		
RHS		1	705.00	0.90		634.50		
Road 4		2	48.00	0.90		86.40		
2nd Cross		2	353.00	0.90		635.40		
						2063.70		
Deduct 90% new slabs						1857.33		
						206.37		
						1029.06	111.30	114534.38
KSRB 5-8.1 : **Providing one line dressing** to granite stone slab / granite stone masonry as per specifications. KBS 5.1.13 (P.No-26, I No-5.17)								
Basic Rate	897.00							
Area Weightage 6%	53.82							
	950.82							
	Sqm							
From item no. 07								
						822.69		
						822.69	**950.82**	**782230.11**
Providing and Fixing **pre cast covering Slab 150mm thick** made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)								
Data rate	2493.00							
	Sqm							
RCC Drain								
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00	1.50		765.00		
						765.00	2493.00	1907145.00
Providing and fixing **RCC precast cover slab of 230mm thick** for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)								
Data rate	**4486.00**							
	Sqm							
For RCC CULVERT COVERING SLAB								
		3	6.10	1.20		21.96		
Attur lake Rd		3	6.50	1.80		35.10		
		11	7.20	1.50		118.80		
Bhaskar Reddy Layout		5	6.50	1.20		39.00		
Best County III		3	6.50	1.20		23.40		
Balaji Layout		6	7.10	1.20		51.12		
		12	6.00	1.80		129.60		
						418.98	4486.00	1879544.28
KSRB 4-1.6 ; Providing and laying in position **plain cement concrete of Mix 1:2:4** with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.No-13,I No-4.3 of PWD BCSR 2018-19)								
Basic Rate	5422.00							

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
4.8*55.47	266.26							
Sub total	5688.26							
6% Area weightage	341.30							
Total	6029.55							
	Cum							
For KERB								
Mahalakshmi Layout								
1st Main Road (W0089)								
2nd Main Road (W0083)		2	170.00	0.20	0.10	6.80		
3rd Main Road (W0081)		2	167.00	0.20	0.10	6.68		
Manjushree Darshini Hotel Rd (W0095)		2	161.00	0.20	0.10	6.44		
Cross Rd		2	230.00	0.20	0.10	9.20		
Ananthapura			64.00	0.20	0.10	2.56		
From Attur lake Rd Upto SWD (W0130)		1	510.00	0.20	0.10	10.20		
Ananthapura								
11th Main Road (W0041)		2	380.00	0.20	0.10	15.20		
Peeple Tree Rd (W0079)		1	400.00	0.20	0.10	8.00		
Bhaskar Reddy Layout								
2nd Main Road		2	162.00	0.20	0.10	6.48		
4th Cross Rd		2	68.00	0.20	0.10	2.72		
4thA Cross Rd (W0024)		2	72.00	0.20	0.10	2.88		
3rd A Cross Rd (W0028)		2	63.00	0.20	0.10	2.52		
2nd Cross Road (W0030)		2	208.00	0.20	0.10	8.32		
2nd A Cross Road (W0032)		2	59.00	0.20	0.10	2.36		
3rd Cross Road (W0026)		2	73.00	0.20	0.10	2.92		
2nd A Main Rd, 2nd Cross Rd		2	91.00	0.20	0.10	3.64		
2nd A Main Rd, 4th Cross Rd		2	140.00	0.20	0.10	5.60		
2nd A Main Rd, 5th A Cross Rd		2	101.00	0.20	0.10	4.04		
2nd A Main Rd, 1st Cross Rd		2	103.00	0.20	0.10	4.12		
2nd A Main Rd, 3rd Cross Rd		2	91.00	0.20	0.10	3.64		
2nd A Main Rd, 5th Cross Rd		2	91.00	0.20	0.10	3.64		
Cross Rd		2	170.00	0.20	0.10	6.80		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00	0.20	0.10	4.80		
Best County II								
2nd Cross Road (W0434)		2	91.00	0.20	0.10	3.64		
Best County III								
1st Main Road(W0787)		2	195.00	0.20	0.10	7.80		
1st Cross Road		2	46.00	0.20	0.10	1.84		
2nd Main Road(W0781)		2	187.00	0.20	0.10	7.48		
Cross Rd		2	147.00	0.20	0.10	5.88		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00	0.20	0.10	4.40		
Cross Rd-1		2	27.00	0.20	0.10	1.08		
2nd Cross Rd		2	108.00	0.20	0.10	4.32		
Cross Rd		2	100.00	0.20	0.10	40.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00	0.20	0.10	12.68		
Burial Ground UptoVillage Road (W0296)		2	293.00	0.20	0.10	11.72		
Veerasagar Hesargatta Road								
LHS		1	786.00	0.20	0.10	15.72		
RHS		1	965.00	0.20	0.10	19.30		
Road 4		2	48.00	0.20	0.10	1.92		
2nd Cross		2	353.00	0.20	0.10	14.12		
Ramp								
Box Culvert for Lake		2	8.00	0.50	0.15	1.20		
						282.66	6029.55	1704312.99
Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (Pg No 112 It No 14.62 of PWD SR 2018-19)								
Basic Rate	1232.00							
Area Weightage 6%	73.92							
	1305.92							
	Nos							
For Footpath								
Veerasagar Hesargatta Road		2	993.00	0.65		1290.90		
2nd Cross		2	353.00	0.30		211.80		
						1502.70	1305.92	1962405.98
Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. (I No-5.30,P No-27 of PWD BCSR 2018-19)								
Basic Rate	408.00							
Area Weightage 6%	24.48							
	432.48							
	Nos							
For KERB								
Mahalakshmi Layout								
1st Main Road (W0089)		2	170.00			340.00		
2nd Main Road (W0083)		2	167.00			334.00		
3rd Main Road (W0081)		2	161.00			322.00		
Manjushree Darshini Hotel Rd (W0095)		2	230.00			460.00		
Cross Rd		2	64.00			128.00		
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00			510.00		
Ananthapura								
11th Main Road (W0041)		2	380.00			760.00		
Peeple Tree Rd (W0079)		1	400.00			400.00		
Bhaskar Reddy Layout								

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd Main Road		2	162.00			324.00		
4th Cross Rd		2	68.00			136.00		
4thA Cross Rd (W0024)		2	72.00			144.00		
3rd A Cross Rd (W0028)		2	63.00			126.00		
2nd Cross Road (W0030)		2	208.00			416.00		
2nd A Cross Road (W0032)		2	59.00			118.00		
3rd Cross Road (W0026)		2	73.00			146.00		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00			182.00		
2nd A Main Rd, 4th Cross Rd		2	140.00			280.00		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00			202.00		
2nd A Main Rd, 1st Cross Rd		2	103.00			206.00		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00			182.00		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00			182.00		
Cross Rd		2	170.00			340.00		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00			240.00		
Best County II								
2nd Cross Road (W0434)		2	91.00			182.00		
Best County III								
1st Main Road(W0787)		2	195.00			390.00		
1st Cross Road		2	46.00			92.00		
2nd Main Road(W0781)		2	187.00			374.00		
Cross Rd		2	147.00			294.00		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00			220.00		
Cross Rd-1		2	27.00			54.00		
2nd Cross Rd		2	108.00			216.00		
Cross Rd		2	100.00			200.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00			634.00		
Burial Ground UptoVillage Road (W0296)		2	293.00			586.00		
Veerasagar Hesargatta Road								
LHS		1	786.00			786.00		
RHS		1	965.00			965.00		
Road 4		2	48.00			96.00		
2nd Cross		2	353.00			706.00		
						12273.00		
						27272.00	**432.48**	**11794594.56**

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19)								
Basic Rate	80.00							
Area Weightage 6%	4.80							
	84.80							
	Sqm							
For KERB								
Mahalakshmi Layout								
1st Main Road (W0089)		2	170.00		0.30	102.00		
2nd Main Road (W0083)		2	167.00		0.30	100.20		
3rd Main Road (W0081)		2	161.00		0.30	96.60		
Manjushree Darshini Hotel Rd		2	230.00		0.30	138.00		
Cross Rd		2	64.00		0.30	38.40		
Ananthapura								
From Attur lake Rd Upto SWD (W0130)		1	510.00		0.30	153.00		
Ananthapura								
11th Main Road (W0041)		2	380.00		0.30	228.00		
Peeple Tree Rd (W0079)		1	400.00		0.30	120.00		
Bhaskar Reddy Layout								
2nd Main Road		2	162.00		0.30	97.20		
4th Cross Rd		2	68.00		0.30	40.80		
4thA Cross Rd (W0024)		2	72.00		0.30	43.20		
3rd A Cross Rd (W0028)		2	63.00		0.30	37.80		
2nd Cross Road (W0030)		2	208.00		0.30	124.80		
2nd A Cross Road (W0032)		2	59.00		0.30	35.40		
3rd Cross Road (W0026)		2	73.00		0.30	43.80		
2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00		0.30	54.60		
2nd A Main Rd, 4th Cross Rd		2	140.00		0.30	84.00		
2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00		0.30	60.60		
2nd A Main Rd, 1st Cross Rd		2	103.00		0.30	61.80		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00		0.30	54.60		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00		0.30	54.60		
Cross Rd		2	170.00		0.30	102.00		
Deo Marvel Layout								
3rd Main Rd								
1st Cross rd (I0173)		2	120.00		0.30	72.00		
Best County II								
2nd Cross Road (W0434)		2	91.00		0.30	54.60		
Best County III								
1st Main Road(W0787)		2	195.00		0.30	117.00		
1st Cross Road		2	46.00		0.30	27.60		
2nd Main Road(W0781)		2	187.00		0.30	112.20		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Cross Rd		2	147.00		0.30	88.20		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		2	110.00		0.30	66.00		
Cross Rd-1		2	27.00		0.30	16.20		
2nd Cross Rd		2	108.00		0.30	64.80		
Cross Rd		2	100.00		0.30	60.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		2	317.00		0.30	190.20		
Burial Ground UptoVillage Road (W0296)		2	293.00		0.30	175.80		
Veerasagar Hesargatta Road								
LHS		1	786.00		0.30	235.80		
RHS		1	965.00		0.30	289.50		
Road 4		2	48.00		0.30	28.80		
2nd Cross		2	353.00		0.30	211.80		
						3681.90	84.80	312225.12
KSRRB M300-14. **Excavation for roadwork in soil** with hydraulic excavator of 0.9 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1km and complete as per specifications. MORTH Specification No.301 (P.No-143, I No-19.14)								
Basic rate	41.00							
6% Area weightage	2.46							
Sub TotalTotal	43.46							
8km Lead	20.48							
Total	63.94							
	Cum							
New Asphalt Road								
Mahalakshmi Layout								
1st Main Road (W0089)		1	276.00	6.80	0.35	656.88		
2nd Main Road (W0083)		1	172.00	6.40	0.35	385.28		
3rd Main Road (W0081)		1	168.00	6.40	0.35	376.32		
1st Main Rd, 1st Cross Rd (W0120)		1	46.00	6.60	0.35	106.26		
Vinayaka Medicals Rd (W0111)		1	272.00	5.40	0.35	514.08		
Centurey Appartment Connecting Rd		1	128.00	6.00	0.35	268.80		
3rd Main Road, 1st Cross Rd (W0106)		1	25.00	6.00	0.35	52.50		
3rd Main Road, 2nd Cross Rd (W0120)		1	22.00	7.00	0.35	53.90		
3rd Main Road, 3rd Cross Rd (W0122)		1	24.00	5.80	0.35	48.72		
3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80	0.35	48.72		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
3rd Main Road, 5th Cross Rd (W0126)		1	20.00	5.80	0.35	40.60		
Manjushree Darshini Hotel Rd (W0095)		1	265.00	5.70	0.35	528.68		
Cross Rd		1	120.00	5.50	0.35	42.00		
Ananthapura								
11th Main Road (W0041)		1	280.00	6.50	0.35	637.00		
Bhaskar Reddy Layout								
2nd Main Road		1	387.00	7.00	0.35	948.15		
2nd A Main Rd (W0022)		1	138.00	6.50	0.35	313.95		
2nd A Main Rd, 1st Cross Rd		1	103.00	6.70	0.35	241.54		
Cross Rd		1	98.00	5.00	0.35	171.50		
2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00	0.35	191.10		
2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20	0.35	197.47		
1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00	0.35	123.90		
1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00	0.35	132.30		
1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00	0.35	153.30		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00	0.35	151.20		
2nd Main 1st Cross Rd		1	53.00	6.50	0.35	120.58		
2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50	0.35	207.03		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70	0.35	279.30		
1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50	0.35	482.30		
1st Main Rd, 4th Cross Rd		1	68.00	6.30	0.30	128.52		
Sneha Giri Dhama House Rd		1	33.70	5.80	0.30	58.64		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80	0.35	205.03		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90	0.35	377.90		
1st Cross Road		1	43.50	5.70	0.35	86.78		
1st Cross Road, Sub Cross Rd		1	23.00	5.60	0.35	45.08		
Best County II								
1st Main Road(W0787)		1	460.00	6.80	0.30	938.40		
2nd Main Road(W0781)		1	235.00	6.50	0.30	458.25		
3rd Main Road(W0775)		1	230.00	6.80	0.30	469.20		
1st B Main Road(W0789)		1	293.00	5.50	0.35	564.03		
1st Cross Road(W0562)		1	97.10	6.60	0.30	192.26		
2nd Cross Road(W0434)		1	91.00	5.80	0.35	184.73		
Cross Rd		1	162.00	6.00	0.35	340.20		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Best County III								
1st Main Road(W1061)		1	200.00	6.00	0.35	420.00		
1st Cross Road(W0572)		1	46.00	5.70	0.30	78.66		
3rd Main Road(W1057)		1	175.00	6.80	0.35	416.50		
2nd Main Road(W1059)		1	193.00	6.30	0.35	425.57		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80	0.35	131.95		
Krishna Enclave Rd (W0163)		1	75.00	5.50	0.35	144.38		
Attur Main Rd		1	182.00	14.20	0.35	904.54		
Cross Rd		1	45.00	6.00	0.35	94.50		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90	0.35	227.15		
Cross Rd-1		1	27.00	5.90	0.35	55.76		
2nd Cross Rd		1	108.00	5.90	0.35	223.02		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.35	1087.31		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.35	1004.99		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00	0.40	284.80		
Ch89-531		1	442.00	9.00	0.40	1591.20		
Ch531-1029		1	498.00	6.30	0.40	1254.96		
New CC Road								
Ananthapura								
1st Cross Road		1	44.50	5.40	0.35	84.11		
2nd Cross Road		1	57.50	5.30	0.35	106.66		
Vijaya Bank Layout								
2nd Cross Road		1	41.00	4.30	0.30	52.89		
3rd Cross Road(W0596)		1	41.00	3.20	0.30	39.36		
4th Cross Road(W0590)		1	38.00	3.00	0.30	34.20		
						20184.84	**63.94**	**1290618.73**
KSRRB 300-58. **Compaction of original ground** by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147,KPWD SR 2018-19)								
Basic Rate	6.00							
AW6%	0.36							
Total	**6.36**							
Mahalakshmi Layout								
1st Main Road (W0089)		1	276.00	6.80		1876.80		
2nd Main Road (W0083)		1	172.00	6.40		1100.80		
3rd Main Road (W0081)		1	168.00	6.40		1075.20		
1st Main Rd, 1st Cross Rd (W0120)		1	46.00	6.60		303.60		
Vinayaka Medicals Rd (W0111)		1	272.00	5.40		1468.80		
Centurey Appartment Connecting Rd		1	128.00	6.00		768.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
3rd Main Road, 1st Cross Rd (W0106)		1	25.00	6.00		150.00		
3rd Main Road, 2nd Cross Rd (W0120)		1	22.00	7.00		154.00		
3rd Main Road, 3rd Cross Rd (W0122)		1	24.00	5.80		139.20		
3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80		139.20		
3rd Main Road, 5th Cross Rd (W0126)		1	20.00	5.80		116.00		
Manjushree Darshini Hotel Rd (W0095)		1	265.00	5.70		1510.50		
Cross Rd		1	120.00	5.50		660.00		
Ananthapura								
11th Main Road (W0041)		1	280.00	6.50		1820.00		
Bhaskar Reddy Layout								
2nd Main Road		1	387.00	7.00		2709.00		
2nd A Main Rd (W0022)		1	138.00	6.50		897.00		
2nd A Main Rd, 1st Cross Rd		1	103.00	6.70		690.10		
Cross Rd		1	98.00	5.00		490.00		
2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00		546.00		
2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20		564.20		
1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00		354.00		
1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00		378.00		
1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00		438.00		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00		432.00		
2nd Main 1st Cross Rd		1	53.00	6.50		344.50		
2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50		591.50		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70		798.00		
1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50		1378.00		
1st Main Rd, 4th Cross Rd		1	68.00	6.30		428.40		
Sneha Giri Dhama House Rd		1	33.70	5.80		195.46		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80		585.80		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90		1079.70		
1st Cross Road		1	43.50	5.70		247.95		
1st Cross Road, Sub Cross Rd		1	23.00	5.60		128.80		
Best County II								
1st Main Road(W0787)		1	460.00	6.80		3128.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd Main Road(W0781)		1	235.00	6.50		1527.50		
3rd Main Road(W0775)		1	230.00	6.80		1564.00		
1st B Main Road(W0789)		1	293.00	5.50		1611.50		
1st Cross Road(W0562)		1	97.10	6.60		640.86		
2nd Cross Road(W0434)		1	91.00	5.80		527.80		
Cross Rd		1	162.00	6.00		972.00		
Best County III								
1st Main Road(W1061)		1	200.00	6.00		1200.00		
1st Cross Road(W0572)		1	46.00	5.70		262.20		
3rd Main Road(W1057)		1	175.00	6.80		1190.00		
2nd Main Road(W1059)		1	193.00	6.30		1215.90		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80		377.00		
Krishna Enclave Rd (W0163)		1	75.00	5.50		412.50		
Attur Main Rd		1	182.00	14.20		2584.40		
Cross Rd		1	45.00	6.00		270.00		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90		649.00		
Cross Rd-1		1	27.00	5.90		159.30		
2nd Cross Rd		1	108.00	5.90		637.20		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80		3106.60		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80		2871.40		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00		712.00		
Ch89-531		1	442.00	9.00		3978.00		
Ch531-1029		1	498.00	6.30		3137.40		
						57293.07	**6.36**	**364383.93**

KSRRB M300-53. **Construction of embankment** with approved material Gravel /Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page 147, Item No 19.60)

Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.30	931.98		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.30	861.42		
Veerasagar Hesargatta Road								
Attur Main Rd		1	442.00	9.00	0.15	596.70		
						2390.10	**344.50**	**823389.45**
Basic Rate Rs.=	325.00							
Add 6% A.W Rs. =	19.50							
Total Rate Rs. =	**344.50**							

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)								
Basic Rate	1882.00							
Area Weightage 6%	112.92							
	1994.92							
	Cum							
New Asphalt Road								
Mahalakshmi Layout								
1st Main Road (W0089)								
2nd Main Road (W0083)		1	276.00	6.80	0.15	281.52		
3rd Main Road (W0081)		1	172.00	6.40	0.15	165.12		
1st Main Rd, 1st Cross Rd (W0120)		1	168.00	6.40	0.15	161.28		
Vinayaka Medicals Rd (W0111)		1	46.00	6.60	0.15	45.54		
Centurey Appartment Connecting Rd		1	272.00	5.40	0.15	220.32		
3rd Main Road, 1st Cross Rd (W0106)		1	128.00	6.00	0.15	115.20		
3rd Main Road, 2nd Cross Rd (W0120)		1	25.00	6.00	0.15	22.50		
3rd Main Road, 3rd Cross Rd (W0122)		1	22.00	7.00	0.15	23.10		
3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80	0.15	20.88		
3rd Main Road, 5th Cross Rd (W0126)		1	24.00	5.80	0.15	20.88		
Manjushree Darshini Hotel Rd (W0095)		1	20.00	5.80	0.15	17.40		
Cross Rd		1	265.00	5.70	0.15	226.58		
Ananthapura			120.00	5.50	0.15	99.00		
11th Main Road (W0041)		1	280.00	6.50	0.15	273.00		
Bhaskar Reddy Layout								
2nd Main Road		1	387.00	7.00	0.15	406.35		
2nd A Main Rd (W0022)		1	138.00	6.50	0.15	134.55		
2nd A Main Rd, 1st Cross Rd		1	103.00	6.70	0.15	103.52		
Cross Rd		1	98.00	5.00	0.15	73.50		
2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00	0.15	81.90		
2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20	0.15	84.63		
1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00	0.15	53.10		
1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00	0.15	56.70		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00	0.15	65.70		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00	0.15	64.80		
2nd Main 1st Cross Rd		1	53.00	6.50	0.15	51.68		
2nd A Main Rd, 2nd Cross Rd		1	91.00	6.50	0.15	88.73		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70	0.15	119.70		
1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50	0.15	206.70		
1st Main Rd, 4th Cross Rd		1	68.00	6.30	0.15	64.26		
Sneha Giri Dhama House Rd		1	33.70	5.80	0.15	29.32		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80	0.15	87.87		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90	0.15	161.96		
1st Cross Road		1	43.50	5.70	0.15	37.19		
1st Cross Road, Sub Cross Rd		1	23.00	5.60	0.15	19.32		
Best County II								
1st Main Road(W0787)		1	460.00	6.80	0.15	469.20		
2nd Main Road(W0781)		1	235.00	6.50	0.15	229.13		
3rd Main Road(W0775)		1	230.00	6.80	0.15	234.60		
1st B Main Road(W0789)		1	293.00	5.50	0.15	241.73		
1st Cross Road(W0562)		1	97.10	6.60	0.15	96.13		
2nd Cross Road(W0434)		1	91.00	5.80	0.15	79.17		
Cross Rd		1	162.00	6.00	0.15	145.80		
Best County III								
1st Main Road(W1061)		1	200.00	6.00	0.15	180.00		
1st Cross Road(W0572)		1	46.00	5.70	0.15	39.33		
3rd Main Road(W1057)		1	175.00	6.80	0.15	178.50		
2nd Main Road(W1059)		1	193.00	6.30	0.15	182.39		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80	0.15	56.55		
Krishna Enclave Rd (W0163)		1	75.00	5.50	0.15	61.88		
Attur Main Rd		1	182.00	14.20	0.15	387.66		
Cross Rd		1	45.00	6.00	0.15	40.50		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90	0.15	97.35		
Cross Rd-1		1	27.00	5.90	0.15	23.90		
2nd Cross Rd		1	108.00	5.90	0.15	95.58		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.15	465.99		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.15	430.71		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00	0.15	106.80		
Ch89-531		1	442.00	9.00	0.15	596.70		
Ch531-1029		1	498.00	6.30	0.15	470.61		

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
							8593.96	1994.92	17144263.68
10	KSRRB M400-17. Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to **wet mix macadam specifications** including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications(P.No-155,I No-20.18)								
	Basic Rate	1888.00							
	Area Weightage 6%	113.28							
		2001.28							
		Cum							
	New Asphalt Road								
	Mahalakshmi Layout								
	1st Main Road (W0089)		1	276.00	6.80	0.200	375.36		
	2nd Main Road (W0083)		1	172.00	6.40	0.200	220.16		
	3rd Main Road (W0081)		1	168.00	6.40	0.200	215.04		
	1st Main Rd, 1st Cross Rd (W0120)		1	46.00	6.60	0.200	60.72		
	Vinayaka Medicals Rd (W0111)		1	272.00	5.40	0.200	293.76		
	Centurey Appartment Connecting Rd		1	128.00	6.00	0.200	153.60		
	3rd Main Road, 1st Cross Rd (W0106)		1	25.00	6.00	0.200	30.00		
	3rd Main Road, 2nd Cross Rd (W0120)		1	22.00	7.00	0.200	30.80		
	3rd Main Road, 3rd Cross Rd (W0122)		1	24.00	5.80	0.200	27.84		
	3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80	0.200	27.84		
	3rd Main Road, 5th Cross Rd (W0126)		1	20.00	5.80	0.200	23.20		
	Manjushree Darshini Hotel Rd (W0095)		1	265.00	5.70	0.200	302.10		
	Cross Rd		1	120.00	5.50	0.200	132.00		
	Ananthapura								
	11th Main Road (W0041)		1	280.00	6.50	0.200	364.00		
	Bhaskar Reddy Layout								
	2nd Main Road		1	387.00	7.00	0.200	541.80		
	2nd A Main Rd (W0022)		1	138.00	6.50	0.200	179.40		
	2nd A Main Rd, 1st Cross Rd		1	103.00	6.70	0.200	138.02		
	Cross Rd		1	98.00	5.00	0.200	98.00		
	2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00	0.200	109.20		
	2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20	0.200	112.84		
	1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00	0.200	70.80		

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00	0.200	75.60		
	1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00	0.200	87.60		
	1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00	0.200	86.40		
	2nd Main 1st Cross Rd		1	53.00	6.50	0.200	68.90		
	2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50	0.200	118.30		
	2nd A Main Rd, 4th Cross Rd		1	140.00	5.70	0.200	159.60		
	1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50	0.200	275.60		
	1st Main Rd, 4th Cross Rd		1	68.00	6.30	0.200	85.68		
	Sneha Giri Dhama House Rd		1	33.70	5.80	0.200	39.09		
	2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80	0.200	117.16		
	Vijaya Bank Layout								
	Main Road(W1085)		1	183.00	5.90	0.200	215.94		
	1st Cross Road		1	43.50	5.70	0.200	49.59		
	1st Cross Road, Sub Cross Rd		1	23.00	5.60	0.200	25.76		
	Best County II								
	1st Main Road(W0787)		1	460.00	6.80	0.200	625.60		
	2nd Main Road(W0781)		1	235.00	6.50	0.200	305.50		
	3rd Main Road(W0775)		1	230.00	6.80	0.200	312.80		
	1st B Main Road(W0789)		1	293.00	5.50	0.200	322.30		
	1st Cross Road(W0562)		1	97.10	6.60	0.200	128.17		
	2nd Cross Road(W0434)		1	91.00	5.80	0.200	105.56		
	Cross Rd		1	162.00	6.00	0.200	194.40		
	Best County III								
	1st Main Road(W1061)		1	200.00	6.00	0.200	240.00		
	1st Cross Road(W0572)		1	46.00	5.70	0.200	52.44		
	3rd Main Road(W1057)		1	175.00	6.80	0.200	238.00		
	2nd Main Road(W1059)		1	193.00	6.30	0.200	243.18		
	Ananthapura								
	Manito Northlite Rd		1	65.00	5.80	0.200	75.40		
	Krishna Enclave Rd (W0163)		1	75.00	5.50	0.200	82.50		
	Attur Main Rd		1	182.00	14.20	0.200	516.88		
	Cross Rd		1	45.00	6.00	0.200	54.00		
	Muneshwara Layout								
	11th Main Road								
	1st Cross Rd		1	110.00	5.90	0.200	129.80		
	Cross Rd-1		1	27.00	5.90	0.200	31.86		
	2nd Cross Rd		1	108.00	5.90	0.200	127.44		
	Ankamma Layout								
	Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.200	621.32		
	Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.200	574.28		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00	0.200	142.40		
Ch89-531		1	442.00	9.00	0.200	795.60		
Ch531-1029		1	498.00	6.30	0.200	627.48		
						11458.61	2001.28	22931895.03
KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications Clause 502 of MORTH V revision(P.No-158,I No-21.6),								
Basic Rate	32.00							
Area Weightage 6%	1.92							
	33.92							
	Sqm							
Mahalakshmi Layout								
1st Main Road (W0089)		1	276.00	6.80		1876.80		
2nd Main Road (W0083)		1	172.00	6.40		1100.80		
3rd Main Road (W0081)		1	168.00	6.40		1075.20		
1st Main Rd, 1st Cross Rd (W0120)		1	46.00	6.60		303.60		
Vinayaka Medicals Rd (W0111)		1	272.00	5.40		1468.80		
Centurey Appartment Connecting Rd		1	128.00	6.00		768.00		
3rd Main Road, 1st Cross Rd (W0106)		1	25.00	6.00		150.00		
3rd Main Road, 2nd Cross Rd (W0120)		1	22.00	7.00		154.00		
3rd Main Road, 3rd Cross Rd (W0122)		1	24.00	5.80		139.20		
3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80		139.20		
3rd Main Road, 5th Cross Rd (W0126)		1	20.00	5.80		116.00		
Manjushree Darshini Hotel Rd (W0095)		1	265.00	5.70		1510.50		
Cross Rd		1	120.00	5.50		660.00		
Ananthapura								
11th Main Road (W0041)		1	280.00	6.50		1820.00		
Bhaskar Reddy Layout								
2nd Main Road		1	387.00	7.00		2709.00		
2nd A Main Rd (W0022)		1	138.00	6.50		897.00		
2nd A Main Rd, 1st Cross Rd		1	103.00	6.70		690.10		
Cross Rd		1	98.00	5.00		490.00		
2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00		546.00		
2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20		564.20		
1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00		354.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00		378.00		
1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00		438.00		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00		432.00		
2nd Main 1st Cross Rd		1	53.00	6.50		344.50		
2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50		591.50		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70		798.00		
1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50		1378.00		
1st Main Rd, 4th Cross Rd		1	68.00	6.30		428.40		
Sneha Giri Dhama House Rd		1	33.70	5.80		195.46		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80		585.80		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90		1079.70		
1st Cross Road		1	43.50	5.70		247.95		
1st Cross Road, Sub Cross Rd		1	23.00	5.60		128.80		
Best County II								
1st Main Road(W0787)		1	460.00	6.80		3128.00		
2nd Main Road(W0781)		1	235.00	6.50		1527.50		
3rd Main Road(W0775)		1	230.00	6.80		1564.00		
1st B Main Road(W0789)		1	293.00	5.50		1611.50		
1st Cross Road(W0562)		1	97.10	6.60		640.86		
2nd Cross Road(W0434)		1	91.00	5.80		527.80		
Cross Rd		1	162.00	6.00		972.00		
Best County III								
1st Main Road(W1061)		1	200.00	6.00		1200.00		
1st Cross Road(W0572)		1	46.00	5.70		262.20		
3rd Main Road(W1057)		1	175.00	6.80		1190.00		
2nd Main Road(W1059)		1	193.00	6.30		1215.90		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80		377.00		
Krishna Enclave Rd (W0163)		1	75.00	5.50		412.50		
Attur Main Rd		1	182.00	14.20		2584.40		
Cross Rd		1	45.00	6.00		270.00		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90		649.00		
Cross Rd-1		1	27.00	5.90		159.30		
2nd Cross Rd		1	108.00	5.90		637.20		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80		3106.60		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80		2871.40		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00		712.00		

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Ch89-531		1	442.00	9.00		3978.00		
	Ch531-1029		1	498.00	6.30		3137.40		
							57293.07	33.92	1943380.93
2	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications Clause 505 of MORTH V revisionusing 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen (P.No-160,I No-21.17.6)								
	Basic rate	6880.00							
	Area Weightage 6%	412.80							
	Total	7292.80							
		Cum							
	New Asphalt Road								
	Mahalakshmi Layout								
	1st Main Road (W0089)		1	276.00	6.80	0.05	93.84		
	2nd Main Road (W0083)		1	172.00	6.40	0.05	55.04		
	3rd Main Road (W0081)		1	168.00	6.40	0.05	53.76		
	1st Main Rd, 1st Cross Rd (W0120)		1	46.00	6.60	0.05	15.18		
	Vinayaka Medicals Rd (W0111)		1	272.00	5.40	0.05	73.44		
	Centurey Appartment Connecting Rd		1	128.00	6.00	0.05	38.40		
	3rd Main Road, 1st Cross Rd (W0106)		1	25.00	6.00	0.05	7.50		
	3rd Main Road, 2nd Cross Rd (W0120)		1	22.00	7.00	0.05	7.70		
	3rd Main Road, 3rd Cross Rd (W0122)		1	24.00	5.80	0.05	6.96		
	3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80	0.05	6.96		
	3rd Main Road, 5th Cross Rd (W0126)		1	20.00	5.80	0.05	5.80		
	Manjushree Darshini Hotel Rd (W0095)		1	265.00	5.70	0.05	75.53		
	Cross Rd		1	120.00	5.50	0.05	33.00		
	Ananthapura								
	11th Main Road (W0041)		1	280.00	6.50	0.05	91.00		
	Bhaskar Reddy Layout								
	2nd Main Road		1	387.00	7.00	0.05	135.45		
	2nd A Main Rd (W0022)		1	138.00	6.50	0.05	44.85		
	2nd A Main Rd, 1st Cross Rd		1	103.00	6.70	0.05	34.51		
	Cross Rd		1	98.00	5.00	0.05	24.50		
	2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00	0.05	27.30		
	2nd A Main Rd, 5th Cross Rd		1	91.00	6.20	0.05	28.21		

Sl	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00	0.05	17.70		
	1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00	0.05	18.90		
	1st Main Rd, 3rd Cross Rd (W0026)		1	73.00	6.00	0.05	21.90		
	1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00	0.05	21.60		
	2nd Main 1st Cross Rd		1	53.00	6.50	0.05	17.23		
	2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50	0.05	29.58		
	2nd A Main Rd, 4th Cross Rd		1	140.00	5.70	0.05	39.90		
	1st Main Rd, 2nd Cross Rd		1	212.00	6.50	0.05	68.90		
	1st Main Rd, 4th Cross Rd		1	68.00	6.30	0.05	21.42		
	Sneha Giri Dhama House Rd		1	33.70	5.80	0.05	9.77		
	2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80	0.05	29.29		
	Vijaya Bank Layout								
	Main Road(W1085)		1	183.00	5.90	0.05	53.99		
	1st Cross Road		1	43.50	5.70	0.05	12.40		
	1st Cross Road, Sub Cross Rd		1	23.00	5.60	0.05	6.44		
	Best County II								
	1st Main Road(W0787)		1	460.00	6.80	0.05	156.40		
	2nd Main Road(W0781)		1	235.00	6.50	0.05	76.38		
	3rd Main Road(W0775)		1	230.00	6.80	0.05	78.20		
	1st B Main Road(W0789)		1	293.00	5.50	0.05	80.58		
	1st Cross Road(W0562)		1	97.10	6.60	0.05	32.04		
	2nd Cross Road(W0434)		1	91.00	5.80	0.05	26.39		
	Cross Rd		1	162.00	6.00	0.05	48.60		
	Best County III								
	1st Main Road(W1061)		1	200.00	6.00	0.05	60.00		
	1st Cross Road(W0572)		1	46.00	5.70	0.05	13.11		
	3rd Main Road(W1057)		1	175.00	6.80	0.05	59.50		
	2nd Main Road(W1059)		1	193.00	6.30	0.05	60.80		
	Ananthapura								
	Manito Northlite Rd		1	65.00	5.80	0.05	18.85		
	Krishna Enclave Rd (W0163)		1	75.00	5.50	0.05	20.63		
	Attur Main Rd		1	182.00	14.20	0.05	129.22		
	Cross Rd		1	45.00	6.00	0.05	13.50		
	Muneshwara Layout								
	11th Main Road								
	1st Cross Rd		1	110.00	5.90	0.05	32.45		
	Cross Rd-1		1	27.00	5.90	0.05	7.97		
	2nd Cross Rd		1	108.00	5.90	0.05	31.86		
	Ankamma Layout								
	Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.05	155.33		
	Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.05	143.57		
	Veerasagar Hesargatta Road								
	Ch0-89		1	89.00	8.00	0.05	35.60		

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Ch89-531		1	442.00	9.00	0.05	198.90		
	Ch531-1029		1	498.00	6.30	0.05	156.87		
							2864.65	7292.80	20891345.04
3	KSRRB 500-7. Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications (P.No-161,I No-21.7)								
	Basic Rate	12.00							
	Area Weightage 6%	0.72							
		12.72							
		Sqm							
	Mahalakshmi Layout								
	1st Main Road (W0089)								
	2nd Main Road (W0083)		1	276.00	6.80		1876.80		
	3rd Main Road (W0081)		1	172.00	6.40		1100.80		
	1st Main Rd, 1st Cross Rd (W0120)		1	168.00	6.40		1075.20		
	Vinayaka Medicals Rd (W0111)		1	46.00	6.60		303.60		
	Centurey Appartment Connecting Rd		1	272.00	5.40		1468.80		
	3rd Main Road, 1st Cross Rd (W0106)		1	128.00	6.00		768.00		
	3rd Main Road, 2nd Cross Rd (W0120)		1	25.00	6.00		150.00		
	3rd Main Road, 3rd Cross Rd (W0122)		1	22.00	7.00		154.00		
	3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80		139.20		
	3rd Main Road, 5th Cross Rd (W0126)		1	24.00	5.80		139.20		
	Manjushree Darshini Hotel Rd (W0095)		1	20.00	5.80		116.00		
	Cross Rd		1	265.00	5.70		1510.50		
	Ananthapura		1	120.00	5.50		660.00		
	11th Main Road (W0041)		1	280.00	6.50		1820.00		
	Bhaskar Reddy Layout								
	2nd Main Road		1	387.00	7.00		2709.00		
	2nd A Main Rd (W0022)		1	138.00	6.50		897.00		
	2nd A Main Rd, 1st Cross Rd		1	103.00	6.70		690.10		
	Cross Rd		1	98.00	5.00		490.00		
	2nd A Main Rd, 3rd Cross Rd (W0055)		1	91.00	6.00		546.00		
	2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.20		564.20		
	1st Main Rd, 2nd A Cross Rd (W0032)		1	59.00	6.00		354.00		
	1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00		378.00		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
1st Main Rd, 3rd Cross Rd (WOO26)		1	73.00	6.00		438.00		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00		432.00		
2nd Main 1st Cross Rd		1	53.00	6.50		344.50		
2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50		591.50		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70		798.00		
1st Main Rd, 2nd Cross Rd (WOO30)		1	212.00	6.50		1378.00		
1st Main Rd, 4th Cross Rd		1	68.00	6.30		428.40		
Sneha Giri Dhama House Rd		1	33.70	5.80		195.46		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80		585.80		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90		1079.70		
1st Cross Road		1	43.50	5.70		247.95		
1st Cross Road, Sub Cross Rd		1	23.00	5.60		128.80		
Best County II								
1st Main Road(W0787)		1	460.00	6.80		3128.00		
2nd Main Road(W0781)		1	235.00	6.50		1527.50		
3rd Main Road(W0775)		1	230.00	6.80		1564.00		
1st B Main Road(W0789)		1	293.00	5.50		1611.50		
1st Cross Road(W0562)		1	97.10	6.60		640.86		
2nd Cross Road(W0434)		1	91.00	5.80		527.80		
Cross Rd		1	162.00	6.00		972.00		
Best County III								
1st Main Road(W1061)		1	200.00	6.00		1200.00		
1st Cross Road(W0572)		1	46.00	5.70		262.20		
3rd Main Road(W1057)		1	175.00	6.80		1190.00		
2nd Main Road(W1059)		1	193.00	6.30		1215.90		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80		377.00		
Krishna Enclave Rd (W0163)		1	75.00	5.50		412.50		
Attur Main Rd		1	182.00	14.20		2584.40		
Cross Rd		1	45.00	6.00		270.00		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90		649.00		
Cross Rd-1		1	27.00	5.90		159.30		
2nd Cross Rd		1	108.00	5.90		637.20		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80		3106.60		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80		2871.40		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00		712.00		
Ch89-531		1	442.00	9.00		3978.00		
Ch531-1029		1	498.00	6.30		3137.40		

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision using40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen (P.No.162, I.No.21.22.6)						57293.07	12.72	728767.85
	Basic Rate	7972.00							
	Area Weightage 6%	478.32							
		8450.32							
		Cum							
	New Asphalt Road								
	Mahalakshmi Layout								
	1st Main Road (W0089)								
	2nd Main Road (W0083)		1	276.00	6.80	0.04	75.07		
	3rd Main Road (W0081)		1	172.00	6.40	0.04	44.03		
	1st Main Rd, 1st Cross Rd (W0120)		1	168.00	6.40	0.04	43.01		
	Vinayaka Medicals Rd (W0111)		1	46.00	6.60	0.04	12.14		
	Centurey Appartment Connecting Rd		1	272.00	5.40	0.04	58.75		
	3rd Main Road, 1st Cross Rd (W0106)		1	128.00	6.00	0.04	30.72		
	3rd Main Road, 2nd Cross Rd (W0120)		1	25.00	6.00	0.04	6.00		
	3rd Main Road, 3rd Cross Rd (W0122)		1	22.00	7.00	0.04	6.16		
	3rd Main Road, 4th Cross Rd (W0124)		1	24.00	5.80	0.04	5.57		
	3rd Main Road, 5th Cross Rd (W0126)		1	24.00	5.80	0.04	5.57		
	Manjushree Darshini Hotel Rd (W0095)		1	20.00	5.80	0.04	4.64		
	Cross Rd		1	265.00	5.70	0.04	60.42		
	Ananthapura								
	11th Main Road (W0041)		1	120.00	5.50	0.04	26.40		
	Bhaskar Reddy Layout								
	2nd Main Road		1	280.00	6.50	0.04	72.80		
	2nd A Main Rd (W0022)		1	387.00	7.00	0.04	108.36		
	2nd A Main Rd, 1st Cross Rd		1	138.00	6.50	0.04	35.88		
	Cross Rd		1	103.00	6.70	0.04	27.60		
	2nd A Main Rd, 3rd Cross Rd (W0055)		1	98.00	5.00	0.04	19.60		
	2nd A Main Rd, 5th Cross Rd (W0063)		1	91.00	6.00	0.04	21.84		
	1st Main Rd, 2nd A Cross Rd (W0032)		1	91.00	6.20	0.04	22.57		
			1	59.00	6.00	0.04	14.16		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
1st Main Rd, 3rd A Cross Rd (W0028)		1	63.00	6.00	0.04	15.12		
1st Main Rd, 3rd Cross Rd (W0026)		1	73.00	6.00	0.04	17.52		
1st Main Rd, 4th A Cross Rd (W0024)		1	72.00	6.00	0.04	17.28		
2nd Main 1st Cross Rd		1	53.00	6.50	0.04	13.78		
2nd A Main Rd, 2nd Cross Rd (W0045)		1	91.00	6.50	0.04	23.66		
2nd A Main Rd, 4th Cross Rd		1	140.00	5.70	0.04	31.92		
1st Main Rd, 2nd Cross Rd (W0030)		1	212.00	6.50	0.04	55.12		
1st Main Rd, 4th Cross Rd		1	68.00	6.30	0.04	17.14		
Sneha Giri Dhama House Rd		1	33.70	5.80	0.04	7.82		
2nd A Main Rd, 5th A Cross Rd (W0067)		1	101.00	5.80	0.04	23.43		
Vijaya Bank Layout								
Main Road(W1085)		1	183.00	5.90	0.04	43.19		
1st Cross Road		1	43.50	5.70	0.04	9.92		
1st Cross Road, Sub Cross Rd		1	23.00	5.60	0.04	5.15		
Best County II								
1st Main Road(W0787)		1	460.00	6.80	0.04	125.12		
2nd Main Road(W0781)		1	235.00	6.50	0.04	61.10		
3rd Main Road(W0775)		1	230.00	6.80	0.04	62.56		
1st B Main Road(W0789)		1	293.00	5.50	0.04	64.46		
1st Cross Road(W0562)		1	97.10	6.60	0.04	25.63		
2nd Cross Road(W0434)		1	91.00	5.80	0.04	21.11		
Cross Rd		1	162.00	6.00	0.04	38.88		
Best County III								
1st Main Road(W1061)		1	200.00	6.00	0.04	48.00		
1st Cross Road(W0572)		1	46.00	5.70	0.04	10.49		
3rd Main Road(W1057)		1	175.00	6.80	0.04	47.60		
2nd Main Road(W1059)		1	193.00	6.30	0.04	48.64		
Ananthapura								
Manito Northlite Rd		1	65.00	5.80	0.04	15.08		
Krishna Enclave Rd (W0163)		1	75.00	5.50	0.04	16.50		
Attur Main Rd		1	182.00	14.20	0.04	103.38		
Cross Rd		1	45.00	6.00	0.04	10.80		
Muneshwara Layout								
11th Main Road								
1st Cross Rd		1	110.00	5.90	0.04	25.96		
Cross Rd-1		1	27.00	5.90	0.04	6.37		
2nd Cross Rd		1	108.00	5.90	0.04	25.49		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		1	317.00	9.80	0.04	124.26		
Burial Ground UptoVillage Road (W0296)		1	293.00	9.80	0.04	114.86		
Veerasagar Hesargatta Road								
Ch0-89		1	89.00	8.00	0.04	28.48		

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	Ch89-531		1	442.00	9.00	0.04	159.12		
	Ch531-1029		1	498.00	6.30	0.04	125.50		
							2291.72	8450.32	19365791.01
5	KSRRB M600-1.Providing and **Constructing dry lean cement concrete mix** CC 1:5:10 base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @0.58cum over a prepared sub-base, coarse and fine aggregate conforming to IS: 383-2016,aggregate cement ratio not to exceed 15:1, Aggregate gradation after blending to be as per Table 600-1,optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications. do- with OPC at 150 kg/cum and coarse aggregate 0.86cum, fine aggregate 0.58cum using Concrete Batch mix Plant at 75 cum/hr capacity with fixed form paver. (P.No-174,I No-21.1.2,KPWD SR 2018-19)								
	Basic Rate	3665.00							
	3*55.47	166.41							
	Sub total	3831.41							
	Area Weightage 6%	229.88							
		4061.29							
		Cum							
	New CC Road								
	Ananthapura								
	1st Cross Road								
	2nd Cross Road		1	44.50	5.40	0.15	36.05		
	Vijaya Bank Layout		1	57.50	5.30	0.15	45.71		
	2nd Cross Road								
	3rd Cross Road(W0596)		1	41.00	4.30	0.15	26.45		
	4th Cross Road(W0590)		1	41.00	3.20	0.15	19.68		
			1	38.00	3.00	0.15	17.10		
							144.98	4061.29	588816.64
	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. (P.No-176,I No-22.6.1)								
	Basic Rate	4916.00							
	7.2*55.47	399.38							
	Sub total	5315.38							
	Area Weightage 6%	318.92							
		5634.31							
		Cum							
	New CC Road								
	Ananthapura								
	1st Cross Road		1	44.50	5.40	0.15	36.05		
	2nd Cross Road		1	57.50	5.30	0.15	45.71		
	Vijaya Bank Layout								

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
2nd Cross Road		1	41.00	4.30	0.15	26.45		
3rd Cross Road(W0596)		1	41.00	3.20	0.15	19.68		
4th Cross Road(W0590)		1	38.00	3.00	0.15	17.10		
						144.98	5634.31	816875.92
KSRRB M800-13.**Road Marking** with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803(P.No-182,I No-24.15)								
Basic Rate	429.00							
Area Weightage 6%	25.74							
	454.74							
	Sqm							
New Asphalt Road								
Mahalakshmi Layout								
1st Main Road (W0089)		2.5	276.00	0.10		69.00		
2nd Main Road (W0083)		2	172.00	0.10		34.40		
3rd Main Road (W0081)		2	168.00	0.10		33.60		
1st Main Rd, 1st Cross Rd (W0120)		2	46.00	0.10		9.20		
Vinayaka Medicals Rd (W0111)		2	272.00	0.10		54.40		
Centurey Appartment Connecting Rd		2	128.00	0.10		25.60		
3rd Main Road, 1st Cross Rd (W0106)		2	25.00	0.10		5.00		
3rd Main Road, 2nd Cross Rd (W0120)		2	22.00	0.10		4.40		
3rd Main Road, 3rd Cross Rd (W0122)		2	24.00	0.10		4.80		
3rd Main Road, 4th Cross Rd (W0124)		2	24.00	0.10		4.80		
3rd Main Road, 5th Cross Rd (W0126)		2	20.00	0.10		4.00		
Manjushree Darshini Hotel Rd (W0095)		2	265.00	0.10		53.00		
Cross Rd		2	120.00	5.50		1320.00		
Ananthapura								
11th Main Road (W0041)		2.5	280.00	0.10		70.00		
Bhaskar Reddy Layout								
2nd Main Road		2.5	387.00	0.10		96.75		
2nd A Main Rd (W0022)		2	138.00	0.10		27.60		
2nd A Main Rd, 1st Cross Rd		2	103.00	0.10		20.60		
Cross Rd		2	98.00	0.10		19.60		
2nd A Main Rd, 3rd Cross Rd (W0055)		2	91.00	0.10		18.20		
2nd A Main Rd, 5th Cross Rd (W0063)		2	91.00	0.10		18.20		

No	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
	1st Main Rd, 2nd A Cross Rd (W0032)		2	59.00	0.10		11.80		
	1st Main Rd, 3rd A Cross Rd (W0028)		2	63.00	0.10		12.60		
	1st Main Rd, 3rd Cross Rd (W0026)		2	73.00	0.10		14.60		
	1st Main Rd, 4th A Cross Rd (W0024)		2	72.00	0.10		14.40		
	2nd Main 1st Cross Rd		2	53.00	0.10		10.60		
	2nd A Main Rd, 2nd Cross Rd (W0045)		2	91.00	0.10		18.20		
	2nd A Main Rd, 4th Cross Rd		2	140.00	0.10		28.00		
	1st Main Rd, 2nd Cross Rd (W0030)		2	212.00	0.10		42.40		
	1st Main Rd, 4th Cross Rd		2	68.00	0.10		13.60		
	Sneha Giri Dhama House Rd		2	33.70	0.10		6.74		
	2nd A Main Rd, 5th A Cross Rd (W0067)		2	101.00	0.10		20.20		
	Vijaya Bank Layout								
	Main Road(W1085)		2	183.00	0.10		36.60		
	1st Cross Road		2	43.50	0.10		8.70		
	1st Cross Road, Sub Cross Rd		2	23.00	0.10		4.60		
	Best County II								
	1st Main Road(W0787)		2.5	460.00	0.10		115.00		
	2nd Main Road(W0781)		2.5	235.00	0.10		58.75		
	3rd Main Road(W0775)		2.5	230.00	0.10		57.50		
	1st B Main Road(W0789)		2	293.00	0.10		58.60		
	1st Cross Road(W0562)		2	97.10	0.10		19.42		
	2nd Cross Road(W0434)		2	91.00	0.10		18.20		
	Cross Rd		2	162.00	0.10		32.40		
	Best County III								
	1st Main Road(W1061)		2	200.00	0.10		40.00		
	1st Cross Road(W0572)		2	46.00	0.10		9.20		
	3rd Main Road(W1057)		2	175.00	0.10		35.00		
	2nd Main Road(W1059)		2	193.00	0.10		38.60		
	Ananthapura								
	Manito Northlite Rd		2	65.00	0.10		13.00		
	Krishna Enclave Rd (W0163)		2	75.00	0.10		15.00		
	Attur Main Rd		2.5	182.00	0.10		45.50		
	Cross Rd		2	44.00	0.10		8.80		
	Muneshwara Layout								
	11th Main Road								
	1st Cross Rd		2	110.00	0.10		22.00		
	Cross Rd-1		2	27.00	0.10		5.40		
	2nd Cross Rd		2	108.00	0.10		21.60		
	Ankamma Layout								
	Main Rd Upto Burial Ground (W0296)		2.5	317.00	0.10		79.25		

Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
Burial Ground UptoVillage Road (W0296)		2.5	293.00	0.10		73.25		
Veerasagar Hesargatta Road								
Lane Marking		2	1029.00	0.10		205.80		
						3108.46	454.74	1413541.10
KSRRB M800-35. **Supply and Installtion of Moulded Shank Raised Pavement Markers** made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97 – DO III Dt 11.06. 1997. The height, width and length shall not exceed 50 mm, 100 mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer.(P.No-187,I No-24.41)								
Basic rate	337.00							
Area Weightage 6%	20.22							
Total	**357.22**							
	Nos							
Mahalakshmi Layout								
1st Main Road (W0089)		3	39.00			117.00		
Manjushree Darshini Hotel Rd (W0095)		2	35.00			70.00		
Ananthapura								
11th Main Road		3	40.00			120.00		
Bhaskar Reddy Layout								
2nd Main Road		3	52.00			156.00		
Vijaya Bank Layout								
Main Road		2	26.00			52.00		
Best County II								
1st Main Road		3	64.00			192.00		
2nd Main Road		3	32.00			96.00		
3rd Main Road		3	32.00			96.00		
1st B Main Road		2	41.00			82.00		
Best County III								
1st Main Road		2	24.00			48.00		
3rd Main Road		2	26.00			52.00		
2nd Main Road		2	26.00			52.00		
Ananthapura								
Attur Main Rd		3	26.00			78.00		
Ankamma Layout								
Main Rd Upto Burial Ground (W0296)		3	45.00			135.00		
Burial Ground UptoVillage Road (W0296)		3	42.00			126.00		
Veerasagar Hesargatta Road								
Studs		2	140.00			280.00		
						1752.00	357.22	625849.44
							Total Construction Cost	175014975.49
							Towards GST 12%	21001797.06
							DPR & PMC Charges 2%	3981300.00

	Description of Items	Unit	No	Length	Width	Depth	Quantity	Rate	Amount
								Sub Total	199998072.55
								Miscellaneous & Rounding Off	1,927.45
								Total	200000000.00

Certificate

1. The workspot was inspected and works is found to be necessary.
2. The area comes within the Bruhat Bangalore Mahanagara Palike limits.
3. The rates adopted based on the PWD SR,Bangalore circle for year 2018-2019, issue rates dated 01-01-2021 and Data Rates

Assistant Engineer
Ward 03
BBMP Bangalore

Asst. Executive Engineer
Yelahanka New Town Sub Division
BBMP Bangalore

Executive Engineer
Yelahanka Division
BBMP Bangalore

Administrative Sanction for Rs. 2000.00 lakhs
Rupees Twenty Crore Only
is accorded under head P-3867
Restoration of 110 villages
roads dmg by RWSSB
Registered as CE No. 17 Subject
to conditions contained in enclosed memo
No. BBMP/EE/YNK/AS/17/2021-22 Dt. 11/02/2022

Executive Engineer

Technical Sanction
Accorded For Rs 2000.00 lakhs only
Head of A/C.....
CER NO :..35..... Dt:26.08.2021

TA

CE

Bhaskng Area in Ward no-03 of Yelaha